



Pergola Assembly Notes

Major components are secured with supplied wood pegs. These are intentionally cut long and can be left as is or cut flush as desired. Roof boards (10 pcs) are attached with supplied steel screws through the top. Pre-Drilling with a 3/16" drill is recommended to prevent splitting. Pergola must be attached firmly to a foundation or pier blocks.

Pergola 1 & 3